
NO_x RECLAIM WORKING GROUP MEETING

FEBRUARY 14, 2019
SCAQMD
DIAMOND BAR, CA

Agenda

- Landing Rule Updates
 - PAR 1134
 - PAR 1110.2
 - PR 1109.1
 - PAR 113
- New Source Review
 - Summary Key Issue #1
 - Summary Key Issue #2
 - Discussion of Key Issue #3 – Ensuring Sufficient Offsets

LANDING RULE UPDATES

3

Command-and-Control BARCT Rulemaking Status

PAR 1134



Gas Turbines

- Public Workshop held November 2018
- Stationary Source Committee Meeting February 15, 2019
- Public Hearing April 2019


PAR 1110.2



Gaseous- and Liquid-Fueled Engines

- Ongoing site visits
- Sent survey questionnaire
- Public Workshop 1st Quarter 2019
- Public Hearing 3rd Quarter 2019

PR 1109.1



Refineries

- Reviewing three proposals for third party verification
 - Contractor selection April Board Meeting
- Working Group Meeting #6 held on Jan. 31, 2019
- Public Hearing Oct. 2019

PR 113



Monitoring, Reporting, and Recordkeeping (MRR)

- Integrated MRR requirements
 - Former RECLAIM
 - Possibly non-RECLAIM
- Initiated preliminary analysis
- Conducted five site visits
- Public Hearing Oct. 2019

4

UPDATE ON NEW SOURCE REVIEW

5

Guiding Principles and Areas of General Agreement

Guiding Principles



Compliance with State and Federal Requirements

No Backsliding

- New and modified sources in RECLAIM must comply with Rule 2005 – New Source Review for RECLAIM
- New and modified sources outside of RECLAIM must comply with Regulation XIII – New Source Review
 - BACT is required for all new and for modified sources with an emission increase
 - Regulation XIII will apply to the first modification post-RECLAIM
- The transition of a facility from RECLAIM to command-and-control is not a NSR event

6

Summary Three NSR Issues

Key Issue #1 For new sources that are permitted in RECLAIM, what are the offset obligations as facilities transition out of RECLAIM?

**OFFSETTING
REQUIREMENTS**

Key Issue #2 When and how pre-modification potential to emit (PTE) is calculated to determine if an emission increase occurs that triggers NSR after facilities transition out of RECLAIM?

PERMITTING

Key Issue #3 How will the SCAQMD ensure that sufficient offsets are available to satisfy NSR requirements?

**OFFSET
AVAILABILITY**

Key Issue #1 Summary (November 8 Working Group Meeting)

For new sources permitted in RECLAIM, what are the offset obligations as facilities transition out of RECLAIM?

**OFFSETTING
REQUIREMENTS**

- NSR requirements for RECLAIM facilities
 - Facilities that were permitted after the start of RECLAIM and facilities with emission increases above their starting allocation have ongoing **holding requirements** to hold RTCs equal to their PTE year-to-year
 - Facilities that existed at the start of RECLAIM only have to hold RTCs equal to their PTE for the first year
- NSR obligations for RECLAIM facilities after transitioning
 - Rule 2005 only has an ongoing holding requirement for some facilities
 - Equivalency to SIP commitment can be demonstrated programmatically
 - RECLAIM NSR does not have an ongoing **offsetting requirement**
 - Rule 2004 requirement to have sufficient RTCs for reconciliation of actual emissions is not an NSR requirement and will not be an ongoing obligation after RECLAIM

Key Issue #2 Summary (December 13 & January 10 Working Group Meetings)

After facilities transition out of RECLAIM, when and how will a pre-modification PTE be calculated to determine if NSR requirements are triggered?

PERMITTING

- Regulation XIII will apply to the first modification post-RECLAIM
- Purpose of calculating a pre-modification PTE is to determine if there is an emissions increase, if so need
 - BACT
 - Offsets
 - Modeling
- Pre-modification PTE needs to be calculated in lbs/day
 - Hierarchy of methodologies will be used to calculate
 - Pre-NSR equipment based on existing Regulation XIII approach (2-year average)

9

KEY ISSUE #3

10

Summary of Three Key NSR Issues

Key Issue #1 For new sources that are permitted in RECLAIM, what are the offset obligations as facilities transition out of RECLAIM?

Key Issue #2 For permits issued without a NO_x PTE, when and how will a baseline be established to determine if an NSR event occurs after facilities transition out of RECLAIM?

Key Issue #3 How will the SCAQMD ensure that sufficient offsets are available to satisfy NSR requirements?

11

Regulation XIII – Purpose and Background

- Ensure facility operations do not interfere with the progress of attainment, and that future economic growth is not unnecessarily restricted
- When a facility applies for a new or modified source, it will be subject to Regulation XIII
- Regulation XIII requires offsets for any permitting action that results in an emission increase ≥ 1 lb/day of any nonattainment air contaminant

12

Possible Consequences if Offsets are Not Available

- If offsets are not available, permits cannot be approved
 - Facility modernization of equipment that meets BACT can be hindered
 - Facilities cannot expand to meet economic demand
 - Can impact regional economy if facility operations are limited or halted
- Limited generation of opportunities
 - Majority of ERCs are generated from shutdowns
 - Incentivizing facilities to shut down equipment to generate ERCs is undesirable
 - Difficult to generate ERCs from over control due to rule-required calculation methodology and BACT discounting

13

Framing Key Issue #3

How will the SCAQMD ensure that sufficient offsets are available to satisfy NSR requirements?

- Under Regulation XIII, if facilities transition out of RECLAIM the only source of offsets is the open market
- Two main questions:
 - Question 1: Can the open market support facilities that transition out of RECLAIM?
 - Question 2: If there are not sufficient offsets in the open market, what are possible options?

**OFFSETS
AVAILABILITY**

14


Question 1: Can the open market support facilities that transition out of RECLAIM?

- Staff Response: The open market cannot support the estimated demand from RECLAIM facilities for future NSR events
 - Insufficient ERCs
 - Supply in the open market
 - Possible demand for ERCs
 - Limited availability

15

ERCs in the Open Market

- Amount of open market ERCs has been on a downward trend for the previous ten years
- Very little change in the previous three years
- Total available NOx ERCs in the open market: ~800 lbs/day[^]



*ERC reduction in 2012 was for a Permit to Construct issued in 2011. The unused ERCs were re-issued to the facility in 2014, pursuant to Rule 1309(g), after the permit was cancelled

[^]Based on the December 2018 listing of active ERCs. Historical Lists available at: <http://www.aqmd.gov/home/permits/emission-reduction-credits/historical-active-erc-and-sterc-lists>

16


Possible NOx Offset Demand from RECLAIM

- New facilities (entered after inception of RECLAIM)
 - RTC hold required at the beginning of each compliance period
 - Amount of RTCs is equal to the post-modification PTE (i.e. pre-modification PTE = zero)
- Existing facilities (in RECLAIM at its inception)
 - RTC hold required only for the first year of operation
 - Amount of RTC hold equals increase in emission, not post-modification PTE
- Emission increases during the 5 year period from 2011–2015
 - Average annual: ~1,000 lbs/day
 - Maximum annual: ~ 2,500 lbs/day

17

Insufficient ERCs - Open Market Challenge

- Amount of ERCs in the open market is not sufficient to satisfy the RECLAIM demand
 - Average RECLAIM demand (1 year) > Total ERCs in open market
 - Supply of ERCs in the open market could be consumed in one year
- Possible average annual debit for RECLAIM: ~1,000 lbs/day*
- Quantity is greater than the 800 lbs/day available in the open market




* Annual RECLAIM demand based on new facilities and existing facilities with new or modified sources.

18

Limited Availability of ERCs in the Open Market

- Not all ERCs in the open market are available for sale
 - Facilities may want to hold on to ERCs for future business growth
 - Facilities held on to ERCs even during peak price in 2009 ~\$400,000 tpy
- Availability is further limited by the small universe of ERC holders
 - ERCs are owned by a total of 21 facilities
 - 6 facilities hold 90% of ERCs




Owner	*ERCs (lbs/day)
PACIFIC L.A. MARINE TERMINAL LLC	500
WEBER METALS INC	82
UCLA	75
VA GREATER LOS ANGELES HEALTHCARE SYS	33
US GOVT, AIR FORCE DEPT, MARCH AFB	25
ORANGE COUNTY SANITATION DISTRICT	18

*Coastal ERCs in the open market February 2018

19

Summary and Recommendation for Question 1




- Former RECLAIM facilities would be allowed to use ERCs in the open market
- Additional source of offsets is needed to support the anticipated demand as facilities transition out of RECLAIM



20

Question 2: If there are not available offsets in the open market, what options are being considered?

Possible sources of offsets for former RECLAIM facilities



21


SCAQMD Internal Bank

- SCAQMD's internal bank provides offsets for
 - Rule 1309.1 facilities (i.e. essential public services) through the Priority Reserve
 - Rule 1304 facilities exempt from offsetting (i.e. NOx PTE less than 4 tons per year)
- Offsets in the internal bank generated mostly from orphan shutdowns
 - Emission reductions from sources that shutdown but did not apply for emission reduction credits (ERCs)

22

NOx Offsets in the SCAQMD Internal Bank

- SCAQMD internal bank currently has >40,000 lbs/day of NOx offsets
- Offsets are SIP approved
 - Real
 - Permanent
 - Enforceable
 - Quantifiable
 - Surplus (discounted annually to BARCT)
- Sufficient NOx offsets in the internal bank to “seed” Large NOx Source Internal Bank



*Projected balance reported in Table 2 of the Final Determination of Equivalency report for the 2016 calendar year in the September 7, 2018 status report on Regulation XIII; Projection is based on the average of total annual debits and the average of total annual credits for the five prior years

23

Rule 1315 (g) Thresholds for Internal Bank – Purpose and Implications

- Rule 1315 (g) establishes annual thresholds for use of offsets from the internal bank
 - Purpose of thresholds is to ensure net emission increases do not exceed the maximum emissions analyzed in the CEQA document
 - Analysis included sources that would be eligible to receive permits under Rule 1309.1 and Rule 1304
 - Thresholds were established based on the net emission increases according to the projected growth in the 2007 Air Quality Management Plan (AQMP)
- If annual threshold is exceeded
 - Offsets cannot be issued from the internal bank – permit moratorium
 - To resume issuing offsets from the internal bank, the cumulative net emission increase must be 10 percent below the corresponding threshold

24

Demonstration of Rule 1315 (g) Table B NOx Thresholds


- Table B thresholds are established from 2011 to 2030 for all five criteria pollutants (VOC, NOx, SOx, CO, and PM10)
- Comparison to annual thresholds is based on minor and major Rule 1309.1 and 1304 facilities that obtain offsets from the Internal Bank
- Net emission increases are calculated according to the cumulative increases and decreases from prior years
- Annual cumulative increases and decreases are reported in the SCAQMD's Regulation XIII Annual Status Report

Year	NOx
2011	0.15
2012	0.25
2013	0.35
2014	0.45
2015	0.53
2016	0.61
2017	0.68
2018	0.76
2019	0.84
2020	0.92
2021	1.00
2022	1.08
2023	1.15
2024	1.27
2025	1.39
2026	1.50
2027	1.62
2028	1.73
2029	1.85
2030	1.96

25

Summary of Cumulative Net Emission Increases/Decreases Since 2011

- Since 2011, the annual cumulative net emission increase has been negative – more emission decreases than increases
 - Annual threshold has never been exceeded
- 2016 cumulative net emission increase for NOx is -2.58 tons/day
 - A total of 3.19 tons/day below the threshold



26

Considerations of SCAQMD Internal Bank NOx Thresholds

- If RECLAIM facilities were to use the internal bank, may need to reevaluate NOx thresholds
 - Thresholds were based on Rule 1309.1 and 1304 facilities
 - 2018 threshold is 0.76 tons per day
 - The projected 2018 cumulative emission increase and decrease is 2.06 tons/day below the threshold
- Potential demand for offsets from RECLAIM facilities could be 2,500 lbs/day (1.25 tons/day) (Slide 17)
- Significant repercussions if an annual threshold is exceeded – permit moratorium

27

Concept for Large NOx Source Internal Bank

- Establish a Large NOx Source Internal Bank for all former RECLAIM facilities and other facilities with a NOx PTE greater than 4 tons/year
- This second internal bank:
 - Provides assurance of a sufficient supply of offsets for Rule 1309.1 and 1304 facilities
 - Maintains existing thresholds for SCAQMD Internal Bank for Rule 1309.1 and 1304 facilities
 - Likely to require NOx offset thresholds – would be specific to sources accessing the bank

28

Concept for Large NO_x Source Internal Bank (Continued)

Seeding the Large NO_x Source Internal Bank

- Offsets from SCAQMD Internal Bank
- Possible RTC conversion to ERCs

Offset Generation

- Generation of offsets from Large NO_x Sources (PTE > 4 tons/year) would go back to the Large NO_x Source Internal Bank

29

Concept for Large NO_x Source Internal Bank (Continued)

Access

- All former RECLAIM would have access
 - Includes small RECLAIM emitters (NO_x PTE less than 4 tons/year)
- Access will also be given to all other sources that are not eligible to use the existing internal bank per Rules 1304 and 1309.1
 - These facilities would have been in RECLAIM had the program continued

Fees

- All facilities would pay fees to obtain offsets

30

Large NOx Source Internal Bank – Next steps

- Determine the amount of offsets needed to seed the bank
 - Analyze the sustainability of SCAQMD Internal Bank and Large NOx Source Internal Bank
 - Can a portion of RTCs help seed the bank?
- New CEQA analysis may be required for the new internal bank
- Need to establish fee

31

Alternative Option – Retain Rule 2005

- Maintain RECLAIM NSR pursuant to Rule 2005
- Continue using RTCs to satisfy RECLAIM NSR requirements
- Would eliminate baseline issues, offset supply issues, and concerns about backsliding
- Generation of RTCs would be based on shutdowns
- RECLAIM facilities would have to reconcile emissions

32

Summary

- Insufficient offsets in the open market to meet the demand for RECLAIM after the transition
- SCAQMD Internal Bank has sufficient offsets to supply RECLAIM facilities
- Offsets in SCAQMD Internal Bank can seed a new Large NOx Source Internal Bank
 - Former RECLAIM facilities will have access to the new internal bank
 - Fee for use
- Alternative options still being considered (e.g., retaining Rule 2005)

33

NSR – Process Moving Forward

Continuing discussions with USEPA regarding RECLAIM NSR transition

Ensure all NSR, AQMP, and CAA requirements will be met after sunset of RECLAIM program

Resume weekly calls with EPA

- Past cancellations due to government shutdown
- Prior discussions focused on Key Issue #1
- Last conference call focused on Key Issue #2

Face-to-face meeting for more extensive discussions tentatively scheduled for March

RECLAIM Working Group Meetings

Monthly working group meetings focused on NSR

Continued discussions with stakeholders

Updates to Stationary Source Committee (SSC)

Quarterly presentation with quarterly RECLAIM update

Monthly written report

34

Contacts

General RECLAIM Questions	New Source Review	
<ul style="list-style-type: none"> • Gary Quinn, P.E. Program Supervisor 909-396-3121 gquinn@aqmd.gov • Kevin Orellana Program Supervisor 909-396-3492 korellana@aqmd.gov 	<ul style="list-style-type: none"> • Michael Morris Planning and Rules Manager 909-396-3282 mmorris@aqmd.gov • Kevin Orellana Program Supervisor 909-396-3492 korellana@aqmd.gov 	<ul style="list-style-type: none"> • Lizabeth Gomez Air Quality Specialist 909-396-3103 lgomez@aqmd.gov • Melissa Gamoning Assistant Air Quality Specialist 909-396-3115 mgamoning@aqmd.gov

35

Contacts

Proposed Rule 1109.1		Proposed Amended Rule 1134
<ul style="list-style-type: none"> • Heather Farr Program Supervisor 909-396-3672 hfarr@aqmd.gov • Jong Hoon Lee Air Quality Specialist 909-396-3903 jhlee@aqmd.gov 	<ul style="list-style-type: none"> • Sarady Ka Air Quality Specialist 909-396-2331 ska@aqmd.gov 	<ul style="list-style-type: none"> • Michael Morris Planning and Rules Manager 909-396-3282 mmorris@aqmd.gov • Uyen-Uyen Vo Air Quality Specialist 909-396-2238 uvo@aqmd.gov

36

Contacts

Proposed Amended Rule 1110.2

- Kevin Orellana
Program Supervisor
909-396-3492
korellana@aqmd.gov
- Rudy Chacon
Air Quality Specialist
909-396-2726
rchacon@aqmd.gov

Proposed Rule 113

- Gary Quinn, P.E.
Program Supervisor
909-396-3121
gquinn@aqmd.gov
- Yanrong Zhu
Air Quality Specialist
909-396-3289
yzhu1@aqmd.gov

Rule 1135

- Michael Morris
Planning and Rules Manager
909-396-3282
mmorris@aqmd.gov
- Uyen-Uyen Vo
Air Quality Specialist
909-396-2238
uvo@aqmd.gov

37

Contacts

Rules 1146, 1146.1, 1146.2

- | | |
|--|---|
| <ul style="list-style-type: none"> • Gary Quinn, P.E.
Program Supervisor
909-396-3121
gquinn@aqmd.gov • Kalam Cheung, Ph.D.
Program Supervisor
909-396-3281
kcheung@aqmd.gov | <ul style="list-style-type: none"> • Lizabeth Gomez
Air Quality Specialist
909-396-3103
lgomez@aqmd.gov • Shawn Wang
Air Quality Specialist
909-396-3319
swang@aqmd.gov |
|--|---|

Rule 1118.1

- Heather Farr
Program Supervisor
909-396-3672
hfarr@aqmd.gov
- Steve Tsumura
Air Quality Specialist
909-396-2549
stsumura@aqmd.gov

38